MYSORE DIVISION.

ADVERTISEMENT.

The 20th September 1889.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 9th October 1889, for constructing an addional line for Silahdars at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1891.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing an additional line for Silahdars at Mysore"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Items.	Per	Rate.	Quantity.
1	Earthwork excavation	C Yd.		635
2	Rough stone in mud filling	"		635
3	Burnt brick in clay	C. Ft.		33,393
4	Do in chunam	"		2,497
5	Slab stones	Sq. Ft.		4,001
6	Doors and windows	"		1,340
7	Coping with brick in mortar	R Ft.		1,573
8	Pointing with chunam	Sq.		6·40
9	Tarring	Do		29 95
10	Wood work, Honne	C. Ft.		456
11	Roofing with honne reepers and 1st class Mangalore tiles, nails, &c., complete.	Sq.		114·46
12	Eave boards	R. Ft.		79
13	Finials	No.		2
14	Ventilating tiles	Do		80
15	Chunam plastering, rough	Sq.		215·81
16	Plastering with mud	"		334·80
17	Flooring with gravel	C. Yd.		119
18	Whitewashing	Sq.		334·80
19	Color washing	Do		215·81
20	Levelling the ground and forming roads including gravelling..	L. S.		

V. H. KARVE, L. C. E.,
Executive Engineer.

NOTICE.

The 16th September 1889.

The following articles, &c., will be sold by public auction on Saturday, 26th October 1889, on the Government Press premises, commencing at 3 P. M.

1 30 inch Perforating Machine, (good 2nd hand.)
1 Lithographic Press.
1 Do ink stand.
2 Type Writers.
2 Binders' Press, wooden.
20 Royal chase.
2 Iron sheets.
2 Lithographic stones.
2 Chairs.
2 Tin cases.
2 Varnish bottles.
1 Large syringe-tin.
1 lot Empty Ink tin.
&c. &c.,

Lot of fancy type perfectly new from Figgins (Surplus stock.)

T. T. LEONARD,
Supt., Mysore Govt. Press.